



**ಸ್ಯ ಮುಕ್ತ ವಿಶ್ವವಿದ್ಯಾನಿಲಯ**  
**ಮುಕ್ತಗಂಗೋತ್ರಿ, ಮೈಸೂರು-570006**  
**ಇಂಜಿನಿಯರಿಂಗ್ ವಿಭಾಗ**

No: KSOU/ES/02/2021-22

Date: 05.05.2021

**ದರಪಟ್ಟಿ ಆಹ್ವಾನ ಪ್ರಕಟಣೆ**

**ವಿಷಯ:** ಕರಾಮುವಿ ನಿಲಯದ ಹಾಸನದಲ್ಲಿರುವ ಪ್ರಾದೇಶಿಕ ಕೇಂದ್ರ ಕಛೇರಿಯ ಆವರಣದಲ್ಲಿ ಬೋರ್‌ವೆಲ್ ಕೊರೆಸುವ ಕಾಮಗಾರಿ ಸಂಬಂಧದ ದರಪಟ್ಟಿ ಆಹ್ವಾನದ ಬಗ್ಗೆ

**ಉಲ್ಲೇಖ:** ಮಾನ್ಯ ಕುಲಪತಿಗಳ ಅನುಮೋದನೆ ದಿನಾಂಕ: 29.04.2021

ಕರಾಮುವಿ ನಿಲಯದ ಹಾಸನದಲ್ಲಿರುವ ಪ್ರಾದೇಶಿಕ ಕೇಂದ್ರ ಕಛೇರಿಯ ಆವರಣದಲ್ಲಿ ಬೋರ್‌ವೆಲ್ ಕೊರೆಸಲು ಉದ್ದೇಶಿಸಲಾಗಿರುತ್ತದೆ.

ಈ ಹಿನ್ನೆಲೆಯಲ್ಲಿ ಈ ಕೆಳಕಂಡಂತೆ ನಮೂದಿಸಿರುವ ಬೋರ್‌ವೆಲ್ ಕೊರೆಸುವ ಕಾಮಗಾರಿಯ ಸಂಬಂಧದ ದರಪಟ್ಟಿಯನ್ನು ಆಹ್ವಾನಿಸಲಾಗಿದ್ದು ಸದರಿ ಕೆಲಸಗಳನ್ನು ನಿರ್ವಹಿಸಲು ತಗಲುವ ವೆಚ್ಚದ ದರವನ್ನು (ನಿಯಮಾನುಸಾರ ಚಾಲ್ತಿ ವರ್ಷದ ತೆರಿಗೆಗಳನ್ನು ಒಳಗೊಂಡಂತೆ) ನಮೂದಿಸಿ ಮೊಹರು ಮಾಡಿದ ಲಕೋಟಿಯ ಮೇಲೆ “ಕರಾಮುವಿ ನಿಲಯದ ಹಾಸನದಲ್ಲಿರುವ ಪ್ರಾದೇಶಿಕ ಕೇಂದ್ರ ಕಛೇರಿಯ ಆವರಣದಲ್ಲಿ ಬೋರ್‌ವೆಲ್ ಕೊರೆಸುವ ಕಾಮಗಾರಿ ಸಂಬಂಧದ ದರಪಟ್ಟಿ” ಎಂದು ನಮೂದಿಸಿ ಕುಲಸಚಿವರು, ಕರಾಮುವಿ, ಮೈಸೂರು ಇವರಿಗೆ ಮುದ್ದಾಗಿ/ಅಂಚೆ ಮೂಲಕ ದಿನಾಂಕ: 15.05.2021 ರ ಒಳಗೆ ಸಲ್ಲಿಸಲು ಕೋರಲಾಗಿದೆ.

Dear Sir,

**Subject: Proposed construction of Borewell and accessories at regional Centre Karnataka State Open University, Hassan**

\*\*\*\*\*

**1. Sealed competitive quotation are invited by the undersigned for the following items of work.**

| Sl. No. | Page No.              | Item No. | Description  | Qty.   | Unit | SR Rate (₹) | Amount (₹) |
|---------|-----------------------|----------|--|--------|------|-------------|------------|
| 1       | BWSSB<br>17-18<br>142 | 4        | Geographical investigation of site for sinking Borewell for supplying drinking water to habitation either through the hand pump, MWS or PWSS by vertical sounding by adopting veener sounding by adopting veener or schlumberger's including reconnaissance of survey of geological formation, geophysical investigation of existing ground water in the vicinity quality, quantity and acceptability of the user including the location of site, recommended department of casing pipe required to seal the top and consolidated formation including an extra depth of 1.00 Mtr in consolidated formation including an extra depth of occupier proposed to trap probable yield and other information required including transportation of instrument and accessories to work site engaging technical personnel labour required etc. complete as directed by Engineer in charge. | 1.00   | Each |             |            |
| 1a.     | BWSSB<br>17-18<br>142 | 9        | Yield testing of borewell at final depth with a minimum of 10 hrs continuously with the help of pump testing unit including the cost of transportation charges, and cost of consumables  | 1.00   | Each |             |            |
| 2.      | BWSSB<br>17-18<br>141 | 1        | Sinking of borewell of 165 mm dia clear using fast rig in all strata including over burden upto 30 M fixing of casting pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicle crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding cost of casing pipes) for piped water supply   |        |      |             |            |
| a       |                       |          | Upto 50 Mtrs   | 100.00 | Rmt  |             |            |
| b       |                       |          | Above 50 Mtrs and upto 100 Mtr   | 100.00 | Rmt  |             |            |
| c       |                       |          | Above 100 Mtrs and upto 150 Mtr  | 100.00 | Rmt  |             |            |
| 3.      | KUWS &<br>DB 25       | 5        | Supplying and fixing 150 mm dia nominal resistance medium block ERW casing pipes of 'B' Class with block electric resistances continuous welded mild steel tubes   | 50     | Rmt  |             |            |

|     |                            |        | Description  | Qty.  | Unit | SR Rate<br>(₹) | Amount<br>(₹) |
|-----|----------------------------|--------|--|-------|------|----------------|---------------|
|     |                            |        | g to IS 1239-1990 (Part-I) amendment 1.5 with latest amendments if any in random length of 4 to 7 mtrs. Both ends threaded conforming to ISS 554-1985 end fitted with a socket and other end with a plastic protection ring pipes supplied should be with ISI making with all lead and lift as per direction of Engineer in charge   |       |      |                |               |
| 4.  | KUWS & DB 25               |        | Supplying and delivering at site submersible pump set for 150 mm borewell and having the cleared duty conditions as detailed and satisfying the performance characteristics for pump and motor as declared to the bureau of Indian standards. The pump set should bear the IS certificate mark ISI 8034-1989 with amendment no.1 (with latest amendment if any) etc. complete as per direction of Engineer in charge | 1.00  | Nos. |                |               |
| 5.  | KUWS & DB 25               |        | Supplying 150 mm CRW collars with all lead and lift  | 3.00  | Nos. |                |               |
| 6.  | KUWS & DB 25               |        | Supplying 150 mm casing cap with all lead and lift   | 1.00  | Nos. |                |               |
| 7.  | KUWS & DB 25               |        | Providing NP/CP 50 mm dia waste unions conforming to ISI specifications and fixing them in position as per directions (Rates includes cost of materials fixtures and conveyance to work spot etc. complete)  | 3.00  | Nos. |                |               |
| 8.  | PWD SR 18-19 102           | 13.73  | Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 50mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.  | 50.00 | Rmt  |                |               |
| 9.  | PWD SR 18-19 94            | 13.6   | Providing and fixing to wall, ceiling and floor galvanised / mild steel tube 50mm dia nominal bore with fittings (medium grade weight 5.24kg/mtr) B class including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.   |       |      |                |               |
|     |                            | a.     | 50 mm dia  | 150   | Rmt  |                |               |
| 10. | PWD SR 18-19 98            | 13.37  | Providing and fixing in position brass gate valve with C.I wheel of approved quality ( screwed end ) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.  | 2.00  | Each |                |               |
| 10. | PWD SR 18-19 100           | 13.52  | Providing and fixing in position 25mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.  |       |      |                |               |
|     |                            | a.     | 25 mm dia  | 3.00  | Each |                |               |
| 11. | Ele Sr 10-11 PWD P. No. 7  | 2.6.3  | Supply and delivery of brand new SPD approved make PVC insulated cable of flat 3 core (sheathed) of nominal cross sectional area 4 mm as per IS 694-1990 with latest amendments with ISI mark etc., complete as per directions of Engineer in charge.  | 250   | Rmt  |                |               |
| 12. | Ele Sr 10-11 PWD P. No. 32 |        | INDOOR TYPE PANEL BOARD: Supplying of panel board units fabricated out of 2 mm thick sheet metal to operate on 3 Phase / 4 wire 50 Hz / 400 / 440 Volts AC Supply -6 to 10 HP 30 Amps etc., complete as per directions of Engineer in charge.  | 1.00  | Each |                |               |
| 13. | Ele Sr 10-11 PWD P. No. 32 |        | Erection electrification and commissioning works of pumpset including aligning and balancing with all necessary erection of materials and labour including supply and erection of two pair of supporting clamps borewell cap cable clips and water tight gland cable protectors bolts, nuts, valve and gauge etc., involved in the job including arranging necessary tools etc.                                      | 1.00  | Each |                |               |
| 14. | Ele Sr 10-11 PWD P. No. 32 |        | Erection of panel board and meter board units with all necessary materials and labour including providing cement concrete foundation bed etc., complete for indoor type etc., complete as per directions of Engineer in charge.  | 1.00  | Each |                |               |
| 15. | Ele Sr 19-20 PWD P. No. 24 | 5.6.6  | Supplying and fixing polished wood board made of not less than 15 mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., 500 x 500 x 65 mm (20" x 20" x 2.5") etc., complete as per directions of Engineer in charge.  | 1.00  | Each |                |               |
| 16. | Ele Sr 19-20 PWD P. No. 27 | 5.17.7 | Supplying and fixing miniature circuit breakers/isolators on existing MCB distribution boards using necessary fixing materials and wiring complete as directed by the Engineer in charge 5 to 30 Amps Triple and Neutral   | 1.00  | Each |                |               |

|     |                                  |                | Description  | Qty. | Unit | SR Rate<br>(₹)       | Amount<br>(₹) |
|-----|----------------------------------|----------------|--|------|------|----------------------|---------------|
| 17  | Ele Sr 19-20<br>PWD<br>P. No. 24 | 5.5.1          | Panel with neutral link switches rewritable fuse type – Havels / Standard / Indo-Asian Crescent-30 or 35 Amps etc., complete as per directions of Engineer in charge.  | 1.00 | Each |                      |               |
| 18. | Ele Sr 19-20<br>PWD<br>P. No. 40 | I No.<br>32, a | Supply and delivery of best indigenous brand new power capacitor as per IS 2834/86 with latest amendments with ISI mark of required capacity tested as approved by the KEB authorities and erection electrification and commissioning of the same at the isolation | 1.00 | Each |                      |               |
|     |                                  |                |  |      |      | Sub Total 1 ₹        |               |
|     |                                  |                |  |      |      | 12 % GST ₹           |               |
|     |                                  |                |  |      |      | Sub Total 2 ₹        |               |
|     |                                  |                |  |      |      | <b>Grand Total ₹</b> |               |

2. Quoted Price:

- The tendered shall quote for items in the format of quotation attached;
- The specification should be drafted to permit the widest possible competition and at the same time present a clear statement of the required standards of workmanship, materials, and performances of the goods to be procured.
- Reference to Brand name and catalogue number should be avoided as far as possible. Where unavoidable, they should be followed by the words 'or at least equivalent'.
- All duties, taxes and other levies payable by the tendered (including tax on the finished goods) shall be included in the rate.
- The rates quoted for each item shall be fixed for the duration of the contract and shall not be subject to any adjustment.
- Rates for supply of partial quantity of an item are not acceptable.
- Corrections if any shall be made by crossing out, initialing, dating and rewriting.
- Cable of facsimile quotations are not acceptable.

3. Each tender must submit only one quotation

4. Evaluation of quotations

- The purchaser will evaluate and compare the quotations determined to be substantially responsible i.e., which are properly signed, and conform to the terms and conditions and specifications in the following manner:
- The evaluation would be done for all the items put together. The items for which no rates have been quoted would be treated as Zero and the total amount would be computed accordingly. Purchaser will award the contract to the responsive tenderer, whose total cost for all the items put together is the lowest.

5. Award of Contract:

- The purchaser will award the contract to the tenderer whose quotation has been determined to be substantially responsible and who has offered the lowest price as per para 4 (b) above.
- The purchaser reserves the right at the time of contract award to increase or decrease the quantities of any or all of the items indicated in Para I 25% without any change in the unit price or any terms and conditions.
- Normal commercial warranty/guarantee if available shall be applicable to the supplied goods;
- Payment shall be made after the delivery of the goods and their acceptance.
- Notwithstanding the above, the purchaser reserves the right to accept or reject any quotations and to cancel the quotation process and reject all quotations at any time prior to the award of the contract.

f quotations:

You are requested to submit the sealed quotations super scribed on the envelope as  
"Quotations for the above due date on 15.05.2021 latest by 5.30 PM hours.

We look forward to receiving your quotations.

Registrar

**Attachment: Schedule of Quotation Form**

ಪ್ರತಿ:-

1. ವಿಶೇಷ ಅಧಿಕಾರಿಗಳು, ಮಾನ್ಯ ಕುಲಪತಿಗಳ ಕಾರ್ಯಾಲಯ ಕರಾಮವಿ, ಮೈಸೂರು ರವರಿಗೆ ಮಾಹಿತಿಗಾಗಿ,
2. ಕುಲಸಚಿವರ ಆಪ್ತ ಸಹಾಯಕರು, ಕರಾಮವಿ, ಮೈಸೂರು
3. ನಿರ್ದೇಶಕರು, ಐಟಿ ವಿಭಾಗ, ಕರಾಮವಿ, ಮೈಸೂರು ರವರಿಗೆ ಈ ಪ್ರಕಟಣೆಯನ್ನು ವಿವಿಿನಿಯದ ಅಧಿಕೃತ ವೆಬ್‌ಸೈಟ್ ನಲ್ಲಿ ದಿನಾಂಕ 15.05.2021 ರವರೆಗೆ ಪ್ರಟಿಸಲು ತಿಳಿಸಲಾಗಿದೆ.
4. ಕಛೇರಿ ಪ್ರತಿ.

## Quotation Form

10,

### Registrar

Karnataka State Open University  
Mukthagangotri, Mysuru – 06.

Dear Sir,

**Subject: Proposed construction of Borewell and accessories at regional  
Centre Karnataka State Open University, Hassan**

\*\*\*\*\*

1. Sealed competitive quotation are invited by the undersigned for the following items of work.

| Sl. No. | Page No.              | Item No. | Description  | Qty.   | Unit | SR Rate (₹) | Amount (₹) |
|---------|-----------------------|----------|--|--------|------|-------------|------------|
| 1       | BWSSB<br>17-18<br>142 | 4        | Geographical investigation of site for sinking Borewell for supplying drinking water to habitation either through the hand pump, MWS or PWSS by vertical sounding by adopting veener sounding by adopting veener or schlumberger's including reconnaissance of survey of geological formation, geophysical investigation of existing ground water in the vicinity quality, quantity and acceptability of the user including the location of site, recommended department of casing pipe required to seal the top and consolidated formation including an extra depth of 1.00 Mtr in consolidated formation including an extra depth of occupier proposed to trap probable yield and other information required including transportation of instrument and accessories to work site engaging technical personnel labour required etc. complete as directed by Engineer in charge. | 1.00   | Each |             |            |
| 1a.     | BWSSB<br>17-18<br>142 | 9        | Yield testing of borewell at final depth with a minimum of 10 hrs continuously with the help of pump testing unit including the cost of transportation charges, and cost of consumables  | 1.00   | Each |             |            |
| 2.      | BWSSB<br>17-18<br>141 | 1        | Sinking of borewell of 165 mm dia clear using fast rig in all strata including over burden upto 30 M fixing of casting pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicle crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding cost of casing pipes) for piped water supply   |        |      |             |            |
| a       |                       |          | Upto 50 Mtrs   | 100.00 | Rmt  |             |            |
| b       |                       |          | Above 50 Mtrs and upto 100 Mtr   | 100.00 | Rmt  |             |            |
| c       |                       |          | Above 100 Mtrs and upto 150 Mtr  | 100.00 | Rmt  |             |            |
| 3.      | KUWS &<br>DB 25       | 5        | Supplying and fixing 150 mm dia nominal resistance medium block ERW casing pipes of 'B' Class with block electric resistances continuous welded mild steel tubes medium grade conforming to IS 1239-1990 (Part-I) amendment 1.5 with latest amendments if any in random length of 4 to 7 mtrs. Both ends threaded conforming to ISS 554-1985 end fitted with a socket and other end with a plastic protection ring pipes supplied should be with ISI making with all lead and lift as per direction of Engineer in charge  | 50     | Rmt  |             |            |
| 4.      | KUWS &<br>DB 25       |          | Supplying and delivering at site submersible pump set for 150 mm borewell and having the cleared duty conditions as detailed and satisfying the performance characteristics for pump and motor as declared to the bureau of Indian standards. The pump set should bear the IS certificate mark ISI 8034-1989 with amendment no.1 (with latest amendment if any) etc. complete as per direction of Engineer in charge   | 1.00   | Nos. |             |            |
| 5.      | KUWS &<br>DB 25       |          | Supplying 150 mm CRW collars with all lead and lift  | 3.00   | Nos. |             |            |
| 6.      | KUWS &<br>DB 25       |          | Supplying 150 mm casing cap with all lead and lift   | 1.00   | Nos. |             |            |
| 7.      | KUWS &<br>DB 25       |          | Providing NP/CP 50 mm dia waste unions conforming to ISI specifications and fixing them in position as per directions (Rates includes cost of materials fixtures and conveyance to work spot etc. complete)  | 3.00   | Nos. |             |            |

|     |                                  |                | Description   | Qty.  | Unit | SR Rate<br>(₹) | Amount<br>(₹) |
|-----|----------------------------------|----------------|---|-------|------|----------------|---------------|
| 8.  | PWD SR<br>18-19<br>102           | 13.73          | Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 50mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.                       | 50.00 | Rmt  |                |               |
| 9.  | PWD SR<br>18-19<br>94            | 13.6           | Providing and fixing to wall, ceiling and floor galvanised / mild steel tube 50mm dia nominal bore with fittings (medium grade weight 5.24kg/mtr) B class including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.  |       |      |                |               |
|     |                                  | a.             | 50 mm dia   | 150   | Rmt  |                |               |
| 10. | PWD SR<br>18-19<br>98            | 13.37          | Providing and fixing in position brass gate valve with C.I wheel of approved quality ( screwed end ) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.   | 2.00  | Each |                |               |
| 10. | PWD SR<br>18-19<br>100           | 13.52          | Providing and fixing in position 25mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.   |       |      |                |               |
|     |                                  | a.             | 25 mm dia   | 3.00  | Each |                |               |
| 11. | Ele Sr 10-11<br>PWD<br>P. No. 7  | 2.6.3          | Supply and delivery of brand new SPD approved make PVC insulated cable of flat 3 core (sheathed) of nominal cross sectional area 4 mm as per IS 694-1990 with latest amendments with ISI mark etc., complete as per directions of Engineer in charge.   | 250   | Rmt  |                |               |
| 12. | Ele Sr 10-11<br>PWD<br>P. No. 32 |                | INDOOR TYPE PANEL BOARD: Supplying of panel board units fabricated out of 2 mm thick sheet metal to operate on 3 Phase / 4 wire 50 Hz / 400 / 440 Volts AC Supply -6 to 10 HP 30 Amps etc., complete as per directions of Engineer in charge.   | 1.00  | Each |                |               |
| 13. | Ele Sr 10-11<br>PWD<br>P. No. 32 |                | Erection electrification and commissioning works of pumpset including aligning and balancing with all necessary erection of materials and labour including supply and erection of two pair of supporting clamps borewell cap cable clips and water tight gland cable protectors bolts, nuts, valve and gauge etc., involved in the job including arranging necessary tools etc. | 1.00  | Each |                |               |
| 14. | Ele Sr 10-11<br>PWD<br>P. No. 32 |                | Erection of panel board and meter board units with all necessary materials and labour including providing cement concrete foundation bed etc., complete as per directions of Engineer in charge.  | 1.00  | Each |                |               |
| 15. | Ele Sr 19-20<br>PWD<br>P. No. 24 | 5.6.6          | Supplying and fixing polished wood board made of not less than 15 mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., 500 x 500 x 65 mm (20" x 20" x 2.5") etc., complete as per directions of Engineer in charge.   | 1.00  | Each |                |               |
| 16. | Ele Sr 19-20<br>PWD<br>P. No. 27 | 5.17.7         | Supplying and fixing miniature circuit breakers/isolators on existing MCB distribution boards using necessary fixing materials and wiring complete as directed by the Engineer in charge 5 to 30 Amps Triple and Neutral  | 1.00  | Each |                |               |
| 17. | Ele Sr 19-20<br>PWD<br>P. No. 24 | 5.5.1          | Supplying and fixing TPST with neutral link switches rewritable fuse type – Havels / Standard / indo-Asian Crescent-30 o 35 Amps etc., complete as per directions of Engineer in charge.  | 1.00  | Each |                |               |
| 18. | Ele Sr 19-20<br>PWD<br>P. No. 40 | I No.<br>32, a | Supply and delivery of best indigenous brand new power capacitor as per IS 2834/86 with latest amendments with ISI mark of required capacity tested as approved by the KEB authorities and erection electrification and commissioning of the same at the isolation  | 1.00  | Each |                |               |
|     |                                  |                |   |       |      | Sub Total 1 ₹  |               |
|     |                                  |                |   |       |      | 12 % GST ₹     |               |
|     |                                  |                |   |       |      | Sub Total 2 ₹  |               |
|     |                                  |                |   |       |      | Grand Total ₹  |               |



**PDF Complete**  
Your complimentary use period has ended.  
Thank you for using PDF Complete.

[Click Here to upgrade to Unlimited Pages and Expanded Features](#)

\_\_\_\_\_ (in figures)

\_\_\_\_\_ (in words)

We agree to execute the above said work in accordance with the technical specifications for a total contract price Rs. \_\_\_\_\_ (in figures) (Rupees \_\_\_\_\_ (in words), within the period specified in the invitations of quotation.

Name: \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_